

Item No.	Description	Quantity	Unit	Unit Price	Item Cost
209.201	Granular Backfill - Bridge - Re-Use Existing Site Material	39	CY		\$ -
214	Fine Grading	1	U		\$ -
304.3	Crushed Gravel - Roadway (Town Supplied)	55	CY		\$ -
304.35	Temporary Crushed Gravel - Detour (Town Supplied)	75	CY		\$ -
502	Removal of Existing Pipe-Arch Culvert Structure	1	U		\$ -
503.201	Temporary Cofferdams & De-Watering	2	U		\$ -
503.202	Shoring of Excavation (S.O.E.)	1	U		\$ -
504.1	Common Bridge Excavation (F)	73	CY		\$ -
504.2	Rock Bridge Excavation (Existing Headwalls & Boulders)	30	CY		\$ -
508	Structural Fill	22	Ton		\$ -
520.12	Concrete Class A, Above Footing (F)	15	CY		\$ -
520.21	Concrete Class B, Footings (F)	18	CY		\$ -
530.3	Waterproofing Concrete Surfaces (F)	232	SF		\$ -
544	Reinforcing Steel (F)	4440	Lbs		\$ -
550.101	Structural Steel (F)	17810	Lbs		\$ -
550.201	Bridge Shoes (Expansion)	4	Ea		\$ -
550.202	Bridge Shoes (Fixed)	4	Ea		\$ -
550.568	Anchor Plates for Timber Deck	28	Ea		\$ -
563.3	Bridge Rail (F)	104	LF		\$ -
568	Structural Timber (F)	6000	BF		\$ -
585.4	Stone Fill, Class D (De-Watering Ops)	20	Ton		\$ -
587.1	Keyed Stone Fill, Bridge	172	CY		\$ -
593.220	Geotextile, Stabilization Cl. 2, Contractors Option	260	SY		\$ -
606.122	Straight 48" Flare FLEAT-SP Terminal Unit TL-3	2	U		\$ -
606.1471	Beam Guardrail Terminal Unit G-2 (40'R) 32' Length	1	U		\$ -
606.1472	Beam Guardrail Terminal Unit G-2 (40'R) 18' Length	1	U		\$ -
606.417	Portable Concrete Barrier for Traffic Control	360	LF		\$ -
619.1	Maintenance of Traffic & Construction Signs	1	U		\$ -
645.531	Silt Fence	400	LF		\$ -
645.71	Stormwater Pollution Prevention Plan & Monitoring	1	U		\$ -
646.41	Turf Establishment w/ Mulch, Tackifier & Humus	250	SY		\$ -
670.045	Construct & Remove Detour	1	U		\$ -
692	Mobilization	1	U		\$ -
				TOTAL	\$ -